

CITY OF CUYAHOGA FALLS - BID TAB_1	
Program:	COOK ST. - HIGH ST. NORTH ALLEY
ORDINANCE NO.....:	ENTER ORDINANCE NUMBER
ADVERTISED DATE.....:	6/20/10, 6/27/10
BID DATE.....:	07/06/10
BASE BID ONLY.....:	\$62,797.90
BASE BID / ALT. 1.....:	
BASE BID / ALT. 2.....:	

FINANCE NO.	ENTER FINANCE NUMBER
FILE NAME...:	ENTER FILE NAME
ENG NO.....:	ENTER ENGINEER NUMBER
CONTRACTOR	TALLMADGE
ADDRESS	
CITY STATE & ZIP	
PHONE & FAX #	

ITEM NO.	SPEC. REF.	ITEM DESCRIPTION	UNIT MEASURE	ESTIMATED QUANTITY	UNIT COST LABOR	UNIT COST MATERIAL	TOTAL UNIT COST	TOTAL COST
1	202	REMOVE EXISTING PAVEMENT	S.Y.	393.00	\$16.85	\$0.00	\$16.85	\$6,622.05
2	202	REMOVE EXISTING WALK	S.F.	200.00	\$3.35	\$0.00	\$3.35	\$670.00
3	203	EXCAVATION	C.Y.	220.00	\$7.15	\$0.00	\$7.15	\$1,573.00
4	204	SUBGRADE COMPACTION	S.Y.	421.00	\$1.00	\$0.00	\$1.00	\$421.00
5	207	INLET PROTECTION	EACH	2.00	\$384.00	\$0.00	\$384.00	\$768.00
6	209	FINE GRADE	S.Y.	421.00	\$2.50	\$0.00	\$2.50	\$1,052.50
7	255	FULL DEPTH PAVEMENT SAWING	L.F.	85.00	\$2.00	\$0.00	\$2.00	\$170.00
8	304	6" LIMESTONE BASE	TON	140.00	\$13.00	\$10.10	\$23.10	\$3,234.00
9	448	ASPHALT PAVEMENT	TON	10.00	\$77.00	\$54.30	\$131.30	\$1,313.00
10	452	6" CONCRETE APPROACH - class MS	S.Y.	55.00	\$31.45	\$16.00	\$47.45	\$2,609.75
11	452	8" CONC. w/ INT. CURB - Class MS	S.Y.	421.00	\$28.00	\$18.20	\$46.20	\$19,450.20
12	603	4" PVC DRAIN PIPE	L.F.	30.00	\$5.90	\$1.00	\$6.90	\$207.00
13	603	YARD DRAIN ASSEMBLY	EACH	2.00	\$284.00	\$150.00	\$434.00	\$868.00
14	603	8" PVC PIPE	L.F.	310.00	\$16.00	\$9.00	\$25.00	\$7,750.00
15	604	ODOT 3A PRECAST CATCH BASIN	EACH	1.00	\$225.00	\$300.00	\$525.00	\$525.00
16	604	ODOT 2-2b PRECAST CATCH BASIN	EACH	2.00	\$225.00	\$250.00	\$475.00	\$950.00
17	604	REPAIR CATCH BASIN	EACH	1.00	\$318.00	\$150.00	\$468.00	\$468.00
18	605	4" UNDERDRAIN	L.F.	556.00	\$9.10	\$0.80	\$9.90	\$5,504.40
19	608	4" CONCRETE WALK	S.F.	200.00	\$3.25	\$3.10	\$6.35	\$1,270.00
20	609	TYPE 2 CURB-GUTTER	L.F.	80.00	\$15.00	\$8.35	\$23.35	\$1,868.00
21	614	MAINTENANCE OF TRAFFIC	LUMP	1.00	\$750.00	\$250.00	\$1,000.00	\$1,000.00
22	623	CONSTRUCTION LAYOUT STAKES	LUMP	1.00	\$1,500.00	\$0.00	\$1,500.00	\$1,500.00
23	624	MOBILIZATION	LUMP	1.00	\$500.00	\$0.00	\$500.00	\$500.00
24	653	FERTILIZER	LB.	50.00	\$0.50	\$0.50	\$1.00	\$50.00
25	653	4" TOPSOIL	C.Y.	60.00	\$13.65	\$11.00	\$24.65	\$1,479.00
26	659	SEEDING AND MULCHING	S.Y.	450.00	\$0.75	\$0.75	\$1.50	\$675.00
27	SPEC.	#8 GRAVEL FOR DRIVES	TON	10.00	\$15.00	\$15.00	\$30.00	\$300.00

CITY OF CUYAHOGA FALLS - BID TAB_1

Program:	COOK ST. - HIGH ST. NORTH ALLEY
ORDINANCE NO.....:	ENTER ORDINANCE NUMBER
ADVERTISED DATE.....:	6/20/10, 6/27/10
BID DATE.....:	07/06/10
BASE BID ONLY.....:	\$57,523.80
BASE BID / ALT. 1.....:	
BASE BID / ALT. 2.....:	

FINANCE NO.	ENTER FINANCE NUMBER
FILE NAME...:	ENTER FILE NAME
ENG NO.....:	ENTER ENGINEER NUMBER
CONTRACTOR	LOCKHART
ADDRESS	800 WATERLOO RD
CITY STATE & ZIP	AKRON, OHIO 44314
PHONE & FAX #	330-745-6520 330-745-5711

ITEM NO.	SPEC. REF.	ITEM DESCRIPTION	UNIT MEASURE	ESTIMATED QUANTITY	UNIT COST LABOR	UNIT COST MATERIAL	TOTAL UNIT COST	TOTAL COST
1	202	REMOVE EXISTING PAVEMENT	S.Y.	393.00	\$2.50	\$0.50	\$3.00	\$1,179.00
2	202	REMOVE EXISTING WALK	S.F.	200.00	\$0.20	\$0.05	\$0.25	\$50.00
3	203	EXCAVATION	C.Y.	220.00	\$6.00	\$1.00	\$7.00	\$1,540.00
4	204	SUBGRADE COMPACTION	S.Y.	421.00	\$0.75	\$0.25	\$1.00	\$421.00
5	207	INLET PROTECTION	EACH	2.00	\$15.00	\$10.00	\$25.00	\$50.00
6	209	FINE GRADE	S.Y.	421.00	\$0.75	\$0.25	\$1.00	\$421.00
7	255	FULL DEPTH PAVEMENT SAWING	L.F.	85.00	\$0.75	\$0.25	\$1.00	\$85.00
8	304	6" LIMESTONE BASE	TON	140.00	\$5.00	\$15.00	\$20.00	\$2,800.00
9	448	ASPHALT PAVEMENT	TON	10.00	\$65.00	\$60.00	\$125.00	\$1,250.00
10	452	6" CONCRETE APPROACH - class MS	S.Y.	55.00	\$30.00	\$13.00	\$43.00	\$2,365.00
11	452	8" CONC. w/ INT. CURB - Class MS	S.Y.	421.00	\$30.00	\$19.80	\$49.80	\$20,965.80
12	603	4" PVC DRAIN PIPE	L.F.	30.00	\$6.00	\$2.00	\$8.00	\$240.00
13	603	YARD DRAIN ASSEMBLY	EACH	2.00	\$100.00	\$50.00	\$150.00	\$300.00
14	603	8" PVC PIPE	L.F.	310.00	\$10.00	\$7.50	\$17.50	\$5,425.00
15	604	ODOT 3A PRECAST CATCH BASIN	EACH	1.00	\$600.00	\$400.00	\$1,000.00	\$1,000.00
16	604	ODOT 2-2b PRECAST CATCH BASIN	EACH	2.00	\$400.00	\$300.00	\$700.00	\$1,400.00
17	604	REPAIR CATCH BASIN	EACH	1.00	\$200.00	\$50.00	\$250.00	\$250.00
18	605	4" UNDERDRAIN	L.F.	556.00	\$3.00	\$3.00	\$6.00	\$3,336.00
19	608	4" CONCRETE WALK	S.F.	200.00	\$4.00	\$1.00	\$5.00	\$1,000.00
20	609	TYPE 2 CURB-GUTTER	L.F.	80.00	\$17.00	\$3.00	\$20.00	\$1,600.00
21	614	MAINTENANCE OF TRAFFIC	LUMP	1.00	\$3,000.00	\$1,142.00	\$4,142.00	\$4,142.00
22	623	CONSTRUCTION LAYOUT STAKES	LUMP	1.00	\$2,000.00	\$642.00	\$2,642.00	\$2,642.00
23	624	MOBILIZATION	LUMP	1.00	\$3,000.00	\$392.00	\$3,392.00	\$3,392.00
24	653	FERTILIZER	LB.	50.00	\$0.50	\$0.50	\$1.00	\$50.00
25	653	4" TOPSOIL	C.Y.	60.00	\$10.00	\$7.00	\$17.00	\$1,020.00
26	659	SEEDING AND MULCHING	S.Y.	450.00	\$0.50	\$0.50	\$1.00	\$450.00
27	SPEC.	#8 GRAVEL FOR DRIVES	TON	10.00	\$10.00	\$5.00	\$15.00	\$150.00

CITY OF CUYAHOGA FALLS - BID TAB_1	
Program:	COOK ST. - HIGH ST. NORTH ALLEY
ORDINANCE NO.....:	ENTER ORDINANCE NUMBER
ADVERTISED DATE.....:	6/20/10, 6/27/10
BID DATE.....:	07/06/10
BASE BID ONLY.....:	\$48,284.25
BASE BID / ALT. 1.....:	
BASE BID / ALT. 2.....:	

FINANCE NO.	ENTER FINANCE NUMBER
FILE NAME...:	ENTER FILE NAME
ENG NO.....:	ENTER ENGINEER NUMBER
CONTRACTOR	PERRIN ASPHALT
ADDRESS	525 DAN ST
CITY STATE & ZIP	AKRON, OHIO 44310
PHONE & FAX #	330-253-1020 330-253-1042

ITEM NO.	SPEC. REF.	ITEM DESCRIPTION	UNIT MEASURE	ESTIMATED QUANTITY	UNIT COST LABOR	UNIT COST MATERIAL	TOTAL UNIT COST	TOTAL COST
1	202	REMOVE EXISTING PAVEMENT	S.Y.	393.00	\$4.00	\$0.00	\$4.00	\$1,572.00
2	202	REMOVE EXISTING WALK	S.F.	200.00	\$0.85	\$0.00	\$0.85	\$170.00
3	203	EXCAVATION	C.Y.	220.00	\$14.00	\$0.00	\$14.00	\$3,080.00
4	204	SUBGRADE COMPACTION	S.Y.	421.00	\$0.25	\$0.25	\$0.50	\$210.50
5	207	INLET PROTECTION	EACH	2.00	\$15.00	\$15.00	\$30.00	\$60.00
6	209	FINE GRADE	S.Y.	421.00	\$1.15	\$0.10	\$1.25	\$526.25
7	255	FULL DEPTH PAVEMENT SAWING	L.F.	85.00	\$0.50	\$0.00	\$0.50	\$42.50
8	304	6" LIMESTONE BASE	TON	140.00	\$8.00	\$14.00	\$22.00	\$3,080.00
9	448	ASPHALT PAVEMENT	TON	10.00	\$120.00	\$55.00	\$175.00	\$1,750.00
10	452	6" CONCRETE APPROACH - class MS	S.Y.	55.00	\$21.00	\$15.00	\$36.00	\$1,980.00
11	452	8" CONC. w/ INT. CURB - Class MS	S.Y.	421.00	\$13.00	\$20.00	\$33.00	\$13,893.00
12	603	4" PVC DRAIN PIPE	L.F.	30.00	\$6.50	\$1.50	\$8.00	\$240.00
13	603	YARD DRAIN ASSEMBLY	EACH	2.00	\$150.00	\$175.00	\$325.00	\$650.00
14	603	8" PVC PIPE	L.F.	310.00	\$12.00	\$8.00	\$20.00	\$6,200.00
15	604	ODOT 3A PRECAST CATCH BASIN	EACH	1.00	\$1,000.00	\$650.00	\$1,650.00	\$1,650.00
16	604	ODOT 2-2b PRECAST CATCH BASIN	EACH	2.00	\$800.00	\$600.00	\$1,400.00	\$2,800.00
17	604	REPAIR CATCH BASIN	EACH	1.00	\$100.00	\$100.00	\$200.00	\$200.00
18	605	4" UNDERDRAIN	L.F.	556.00	\$4.50	\$1.75	\$6.25	\$3,475.00
19	608	4" CONCRETE WALK	S.F.	200.00	\$2.50	\$1.25	\$3.75	\$750.00
20	609	TYPE 2 CURB-GUTTER	L.F.	80.00	\$16.75	\$6.25	\$23.00	\$1,840.00
21	614	MAINTENANCE OF TRAFFIC	LUMP	1.00	\$200.00	\$0.00	\$200.00	\$200.00
22	623	CONSTRUCTION LAYOUT STAKES	LUMP	1.00	\$200.00	\$50.00	\$250.00	\$250.00
23	624	MOBILIZATION	LUMP	1.00	\$250.00	\$250.00	\$500.00	\$500.00
24	653	FERTILIZER	LB.	50.00	\$0.25	\$0.25	\$0.50	\$25.00
25	653	4" TOPSOIL	C.Y.	60.00	\$19.00	\$15.00	\$34.00	\$2,040.00
26	659	SEEDING AND MULCHING	S.Y.	450.00	\$1.00	\$1.00	\$2.00	\$900.00
27	SPEC.	#8 GRAVEL FOR DRIVES	TON	10.00	\$10.00	\$10.00	\$20.00	\$200.00

SPAANO

	CITY OF CUYAHOGA FALLS - BID TAB_1
Program:	COOK ST. - HIGH ST. NORTH ALLEY
ORDINANCE NO.....:	ENTER ORDINANCE NUMBER
ADVERTISED DATE.....:	6/20/10, 6/27/10
BID DATE.....:	07/06/10
BASE BID ONLY.....:	\$51,537.00
BASE BID / ALT. 1.....:	
BASE BID / ALT. 2.....:	

FINANCE NO.	ENTER FINANCE NUMBER
FILE NAME...:	ENTER FILE NAME
ENG NO.....:	ENTER ENGINEER NUMBER
CONTRACTOR	SPANO BROS
ADDRESS	2595 PRESSLER RD
CITY STATE & ZIP	AKRON, OHIO 44312
PHONE & FAX #	330-645-1544 330-645-1404

ITEM NO.	SPEC. REF.	ITEM DESCRIPTION	UNIT MEASURE	ESTIMATED QUANTITY	UNIT COST LABOR	UNIT COST MATERIAL	TOTAL UNIT COST	TOTAL COST
1	202	REMOVE EXISTING PAVEMENT	S.Y.	393.00	\$2.00	\$2.00	\$4.00	\$1,572.00
2	202	REMOVE EXISTING WALK	S.F.	200.00	\$1.00	\$1.00	\$2.00	\$400.00
3	203	EXCAVATION	C.Y.	220.00	\$5.00	\$5.00	\$10.00	\$2,200.00
4	204	SUBGRADE COMPACTION	S.Y.	421.00	\$1.00	\$0.00	\$1.00	\$421.00
5	207	INLET PROTECTION	EACH	2.00	\$10.00	\$10.00	\$20.00	\$40.00
6	209	FINE GRADE	S.Y.	421.00	\$1.00	\$0.00	\$1.00	\$421.00
7	255	FULL DEPTH PAVEMENT SAWING	L.F.	85.00	\$1.00	\$1.00	\$2.00	\$170.00
8	304	6" LIMESTONE BASE	TON	140.00	\$1.00	\$18.00	\$19.00	\$2,660.00
9	448	ASPHALT PAVEMENT	TON	10.00	\$50.00	\$50.00	\$100.00	\$1,000.00
10	452	6" CONCRETE APPROACH - class MS	S.Y.	55.00	\$20.00	\$20.00	\$40.00	\$2,200.00
11	452	8" CONC. w/ INT. CURB - Class MS	S.Y.	421.00	\$20.00	\$26.00	\$46.00	\$19,366.00
12	603	4" PVC DRAIN PIPE	L.F.	30.00	\$2.00	\$2.00	\$4.00	\$120.00
13	603	YARD DRAIN ASSEMBLY	EACH	2.00	\$50.00	\$50.00	\$100.00	\$200.00
14	603	8" PVC PIPE	L.F.	310.00	\$5.00	\$5.00	\$10.00	\$3,100.00
15	604	ODOT 3A PRECAST CATCH BASIN	EACH	1.00	\$1,000.00	\$1,000.00	\$2,000.00	\$2,000.00
16	604	ODOT 2-2b PRECAST CATCH BASIN	EACH	2.00	\$800.00	\$200.00	\$1,000.00	\$2,000.00
17	604	REPAIR CATCH BASIN	EACH	1.00	\$200.00	\$100.00	\$300.00	\$300.00
18	605	4" UNDERDRAIN	L.F.	556.00	\$4.00	\$3.00	\$7.00	\$3,892.00
19	608	4" CONCRETE WALK	S.F.	200.00	\$2.00	\$1.00	\$3.00	\$600.00
20	609	TYPE 2 CURB-GUTTER	L.F.	80.00	\$10.00	\$10.00	\$20.00	\$1,600.00
21	614	MAINTENANCE OF TRAFFIC	LUMP	1.00	\$1,000.00	\$0.00	\$1,000.00	\$1,000.00
22	623	CONSTRUCTION LAYOUT STAKES	LUMP	1.00	\$1,000.00	\$0.00	\$1,000.00	\$1,000.00
23	624	MOBILIZATION	LUMP	1.00	\$3,000.00	\$0.00	\$3,000.00	\$3,000.00
24	653	FERTILIZER	LB.	50.00	\$0.25	\$0.25	\$0.50	\$25.00
25	653	4" TOPSOIL	C.Y.	60.00	\$15.00	\$5.00	\$20.00	\$1,200.00
26	659	SEEDING AND MULCHING	S.Y.	450.00	\$1.00	\$1.00	\$2.00	\$900.00
27	SPEC.	#8 GRAVEL FOR DRIVES	TON	10.00	\$10.00	\$5.00	\$15.00	\$150.00